



RAMP DETAIL  
SCALE: 6"=1'-0"

CONSTRUCTION NOTES:

- CUT HOLE THROUGH WALL 72.5"H x 38.5"W
- INSTALL PASS THRU THROUGH WALL
- LAG PASS THRU TO THE FLOOR (4) PLCS
- RE-SEAL WALL OPENING AS REQUIRED
- INSTALL ADJUSTABLE TRIM FLANGE
- 16 GA STAINLESS STEEL TYPE 304
- 1/4" TEMPERED SAFETY GLASS (BOTH SIDES)
- NEOPRENE GASKET DOOR SEALS

FOR APPROVAL ONLY

ONE (1) SET OF APPROVAL PRINTS MUST BE SIGNED AND RETURNED TO TBJ INC. BEFORE EQUIPMENT CAN BE RELEASED FOR PRODUCTION

- APPROVED AS DRAWN FOR FABRICATION
- NOT APPROVED - REVISE & RESUBMIT FOR FINAL APPROVAL

SIGNED \_\_\_\_\_  
DATE \_\_\_\_\_

UNLESS OTHERWISE SPECIFIED		B	40.00 WAS 36.00, UPDATED WALL THICKNESS, 250 WAS 4.00	BAB	12/8/14
TOLERANCES IN INCHES:		A	ADDED SECOND CABINET TO TOP	BAB	11/21/14
FRACTIONAL ± 1/32		LET	REVISION	BY	DATE
ANGULAR ± 0°25'				1671 ORCHARD DRIVE	
ONE DECIMAL ± 0.063				CHAMBERSBURG, PA 17201	
TWO DECIMAL ± 0.031				Phone: (717) 261-9700 www.tbjinc.com	
THREE DECIMAL ± 0.015		SCALE 1-1/2"=1'-0"	2338-3	DRAWN BY	BAB
		REF DWG - R10194		DATE	11-3-14
PRD. RELEASE	NAME	DATE	CUSTOM CART PASS THRU		
APPR. RELEASE			ROUGH-IN ASSEMBLY		
REVIEWED BY	NES	12-8-14	R14180		
ENG APPR.					